



Test Report: EPP-150-27

150W Single Output with PFC Function

■ DESIGN VERIFY TEST

Output Function Test
Input Function Test
Protection Function Test
Control Function Test
Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test
E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

DESIGN VERIFY TEST
OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 240 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 44.4 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 26.46 V ~ 28.35 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	25.694 V ~ 29.487 V / 230 VAC 25.695 V ~ 29.487 V / 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 1 % ~ -1 % (Max)	I/P : 100VAC / 264 VAC O/P : FULL / MIN LOAD Ta : 25°C	V1 : 0.03 % ~ -0.03 %	P
4	LINE REGULATION	V1 : 0.5 % ~ -0.5 % (Max)	I/P : 100VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0.03 % ~ -0.03 %	P
5	LOAD REGULATION	V1 : 1 % ~ -1 % (Max)	I/P : 230 VAC O/P : FULL ~ MIN LOAD Ta : 25°C	V1 : 0.03 % ~ -0.03 %	P
6	SET UP TIME	230VAC : 1000 ms (Max) 115VAC : 2000 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC / 390 ms 115VAC / 750 ms	P
7	RISE TIME	230VAC : 30 ms (Max) 115VAC : 30 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC / 7 ms 115VAC / 7 ms	P
8	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC / 22 ms 115VAC / 21 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
10	DYNAMIC LOAD	V1 : 2700 mVp-p	I/P : 230 VAC (1).O/P : FULL / Min LOAD 90%DUTY / 1KHZ (2).O/P : FULL / Min LOAD 90%DUTY / 3KHZ (3).O/P : FULL / Min LOAD 90%DUTY / 5KHZ (4).O/P : FULL / Min LOAD 50%DUTY / 120HZ Ta : 25°C	(1)298 mVp-p (2)252 mVp-p (3)265 mVp-p (4)2560 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C I/P : LOW-LINE -3V= 87 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	59V~264V TEST : OK	P
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100 VAC ~ 264 VAC O/P : FULL -MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.98 / 115 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.963 / 230 VAC PF= 0.995 / 115 VAC	P
4	EFFICIENCY	92 % (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	92.53 %	P
5	INPUT CURRENT	230V/ 1 A (TYP) 115V/ 1.8 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.75 A/ 230 VAC I = 1.49 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 80 A (TYP) COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 70 A/ 230 VAC	P
7	LEAKAGE CURRENT	< 2 mA / 240 VAC	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.11 mA N-FG : 0.11 mA	P
8	NO LOAD CONSUMPTION	< 0.5 W	I/P : 115VAC I/P : 230VAC O/P : NO LOAD Ta : 25°C	< 0.37 W < 0.42 W	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105% - 145 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	125 %/ 230 VAC 125 %/ 115 VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH1 : 30.2V ~ 34.05 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	31.834V/ 230 VAC 31.821V/ 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : RTH2 : 110 ± 10°C TSW1 : 110 ± 5°C O.T.P. NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage → recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup Mode	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	AUXILIARY POWER (AUX)	12V@0.3A for driver a fan, tolerance ± 10% at main output 100% load	I/P : 230 VAC O/P : FULL LOAD	FAN VOLTAGE : 12.546V	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q6 Rated : STD10NM60N 8A/650V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 448 V (2) 436 V (3) 432 V	P
2	Diode Peak Voltage	Q100 Rated : PFR30L100CT 30A/100V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 68.4 V (2) 27 V (3) 67.2 V	P
3	Input Capacitor Voltage	C5 Rated : 100u/420V 105°C 18*25 PAG	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 408 V (2) 406 V (3) 408 V	P
4	Control IC Voltage Test	U 1 Rated : NCP1605 10V~20V U900 Rated : L6599AD 8.85V~16V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 16.9 V (2) 17.8 V (3) 13.9 V (4) 15 V (5) 15 V (6) 13.9 V	P
5	Power Transistor (D to S) or (C to E) Peak Voltage	Q 1 Rated : STF28NM50N 21A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 478 V (2) 448 V (3) 452 V	P

SAFETY & E.M.C. TEST
SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min I/P-FG : 2 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P : 3.6 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 1.684 mA I/P-FG : 0.784 mA O/P-FG : 0.276 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C / 70%RH	I/P-O/P : 30 GΩ I/P-FG : 30 GΩ O/P-FG : 30 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	27mΩ	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A CLASS D	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N : 2KV L,N-PE : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC	OK	P
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -35°C~ +55°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec	OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	EPP-150-24:SUPPOSE C106 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 50 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta= 50 °C LIFE TIME	(1) 2888088HRS (2) 483044HRS (3) 493097HRS (4) 496530HRS	P
10	MTBF	MIL-HDBK-217F NOTICE S2 PARTS COUNT TOTAL FAILURE RATE : 207.1 KHRS		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 30,000 hours @ TA 50°C		P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2012/5/7	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG
2012/5/30	PRODUCT SAMPLE	PASS	SANFORD SU	VINCENT TSENG

2009/08/04 A50-F023